

RULE 20:10:13:56
 SCHEDULE D-2
 Plant Addition and Retirement for Test Period
 Test Year Ending December 31, 2013
 Utility: MidAmerican Energy Company
 Docket No. EL14-XXX

Individual Responsible: Mary Jo Anderson

Line No	Description (a)	In-Service Date (b)	South Dakota Amount (c)
Major Additions			
1	Neal 4 Scrubber Baghouse	11/27/2013	804,591
2	This project is for the supply and installation of a dry scrubber and baghouse at Neal Unit 4 as part of MidAmerican's approved Environmental Plan. The project will reduce SO2 and particulate, and provide for enhanced mercury reductions to help meet pending EPA regulatory requirements in 2014. An activated carbon injection system and SNCR will be installed under separate AFE's.		
3	Pinehurst Trail Extension Phase 4	9/12/2013	109,057
4	Extend underground electric distribution facilities to new 23-lot residential subdivision in Dakota Dunes, SD. The scope of work includes installation of 3200' of 1-phase cable, 6 pad-mount transformers, one pad-mounted switchgear, and extending 2500' of 3-phase 4/0 cable to extend the circuit feeder that will eventually tie E Pinehurst Trail to E Sawgrass Trail.		
5	2013 Quad Cities Nuclear Power Station In Service	Various 2013 dates	126,282
6	Various capital projects placed in service by Exelon Generation at the Quad Cities Nuclear Power Station during 2013.		
7	Vienna 2 Wind Farm		
8	Construction of 44.6 MW of additional generation at the Vienna site for Vienna II including site acquisition, turbine supply, and related equipment.	12/4/2013	549,649
Major Retirements			
9	There were no major retirements in the test year.		

Source: Continuing Property Records (CPR) query